



HEATIZON SYSTEMS ELEMENT TESTER (NI-113)

Description

Heatizon Systems Element Tester is designed to help insure that the secondary voltage and amperage across the Cold Leads and Tuff Cable heating element or Colds Leads and Z Mesh heating element or the Floorizwarm heating element remains the same as they were immediately following installation. Conducting tests on the Cold Leads and Tuff Cable, Z Mesh, or Floorizwarm heating element will help insure that a third party or an unknown event has not adversely impacted or otherwise compromised the Cold Lead or heating element.



Uses

The Element Tester should be used to record the voltage and amperage across the Cold Leads and Tuff Cable, Z Mesh, or Floorizwarm heating elements:

- Immediately after the Cold Lead and Tuff Cable, Z Mesh, or Floorizwarm heating element has been installed
- Immediately following the covering of the heating element and prior to installing the Control Box
- Immediately following the energizing of the system

Heatizon Systems
4403 South 500 West
Murray, UT 84123
www.heatizon.com



Phone (801) 293-1232
Fax (801) 293-3077
Toll Free (888) 239-1232